

Tevatron Beam Position Monitor Upgrade

Stephen Wolbers

(for the Tevatron BPM Upgrade Project)

PAC05, Knoxville, TN

May 16-20, 2005

Outline

- Motivation for TeV BPM Upgrade
- TeV BPM Upgrade Design and Implementation
- Performance of New BPM System
- Conclusions

Motivation for Upgrade

- Old Tevatron BPM electronics was not accurate, precise or reliable enough for the Tevatron, nor was it able to measure pbar positions.
 - Old system was built in the early 1980's and is showing its age.
 - Resolution of 150 microns.
 - Uses old networking/controls protocols
 - No pbar position measurements.
- Pickups in the tunnel not to be modified!

New System Requirements

- Stable, accurate, precise measurements.
 - Aiming for <10 micron (1 sigma) precision for best proton position measurement.
- Reliable hardware and software.
- Software to collect and use the data.
- Measurement of antiproton positions (new capability).
 - Requires that both ends of pickups be instrumented (twice as many electronics channels).
 - Turn-by-turn (wide-band) and close orbit (narrow-band) position measurements

Key Specifications (Protons):

Measurement Range: $\pm 15\text{mm}$

Absolute Position Accuracy: $< 1.0\text{ mm}$

Long Term Position Stability: $< 0.05\text{ mm}$

Best Orbit Position Resolution: $< 0.02\text{mm}$

Position Linearity: $< 1.5\%$

Relative Position Accuracy: $< 5\%$

Intensity Stability: $< 2\%$

Key Specifications (Pbars):

Measurement Range: $\pm 15\text{mm}$

Absolute Position Accuracy: $< 1.0\text{ mm}$

Long Term Position Stability: $< 0.02\text{ mm}$

Best Orbit Position Resolution: $< 0.05\text{mm}$

Position Linearity: $< 1.5\%$

Relative Position Accuracy: $< 5\%$

Intensity Stability: $< 2\%$

System Design

- **Schedule:**
 - To be effective and useful, the BPM upgrade had to be accomplished quickly.
- **Technology:**
 - A decision was made to use essentially the same digitizer board (made by Echotek Corp.) as was used in the Recycler BPM upgrade.
 - This board was also chosen for the NUMI, transfer line, and Main Injector BPM upgrades.


System Design

- **Position measurement**
 - The 53 MHz component of the BPM response is used to measure position.
- **Analog signal**
 - The analog signal is filtered and attenuated on a special purpose filter board. The bandpass filters are 53 MHz with width of 7 MHz.
 - An impulse response time of 400ns was required to allow for pbar measurements using timing (rather than proton signal subtraction)
 - See Poster/Paper from Bob Webber for details of the timing technique.


System Design

- **Anti-proton position measurements:**
 - The pickups in the Tevatron have directionality of 26dB.
 - Both ends are read out with the new Tevatron BPM electronics.
 - The proton signal (currently) is significantly larger (factor 10) than the antiproton signal.
 - Even with the 26dB directionality, the antiproton ends of the pickups see approximately equal contributions from antiproton and proton and we need to separate them to make antiproton measurements (in frequency space).
 - See Rob Kutschke's poster/paper for details of the proton cancellation technique.

Block Diagram - vertical BPM




VME Crate Layout



Project Dates

- 9/22/03: Requirements review
- 12/19/03: Technology choice review
- 3/11/04: Place Echotek Order
- 5/14/04: Electronics Design Review
- 8/20/04: First Production Echotek boards arrive
- 8/6/04: Install prototype crate in Tevatron
- 11/23/04: Install first production system in A3
- 2/7/05: Finish commissioning A3
- 5/15/05: Finish commissioning all 27 systems


Commissioning of Houses



System Performance

- Closed orbit
 - Average over all bunches and over many turns (1 KHz bandwidth)
 - Proton and anti-proton positions
 - Best resolution $\sim 7\text{-}10\ \mu\text{m}$
 - Vertical BPMs show better resolution
 - This is thought to be due to beam motion in the horizontal plane


Closed Orbit HA32 Shot on Feb 18, 2005



$$Sum = |A| + |B|$$


$$A = (I_A, Q_A)$$

$$B = (I_B, Q_B)$$




$$P = 26 \frac{|A| - |B|}{|A| + |B|}$$

Closed Orbit HA32 Shot on Feb 18, 2005



Detail during **proton injection** and **anti-proton injection**.


Can see injection bumps during proton injection.



During pbar injection can see injections, cogging and a small instrumental effects.

Pbar Position Measurement Technique


Closed Orbit HA32 Shot on Feb 18, 2005



Cancellation of proton contamination on Pbar cables:

$$A'_{Pbar} = A_{Pbar} - aA_P - bB_P$$



$$B'_{Pbar} = B_{Pbar} - cB_P - dA_P$$




a, b, c, d determined empirically using the opening of the helix.

Using corrected values, compute sum and position as for protons.


Closed Orbit HA32 Shot on Feb 18, 2005



Resolution for A3 BPMs, Feb 14, 2005







TeV BPM - 36 Bunch Closed Orbit Resolution







System Performance

- Turn by turn
 - Injection, 150 GeV
 - Single bunch or uncoalesced beam
 - Can see synchrotron motion, betatron motion, quadrupole oscillations of bunch in the bucket, HV coupling, plus some instrumental artifacts

Position for H BPMs in A3, Feb 6/05, Coalesced



Position for V BPMs in A3, Feb 6/05, Coalesced







1.1 mm full vertical scale





0.6 mm full vertical scale

- Injection TBT; 150 GeV; 8192 turns.
- One coalesced bunch. HEP shot after all tuning.

Detail of Mod(FT) for H BPMs in A3, Feb 6/05, Coalesced



Detail of Mod(FT) for V BPMs in A3, Feb 6/05, Coalesced



1113 / 5 Artifacts





Bin Size: ~ 3 Hz

Resolution: $0.3 \mu\text{m}/\text{sqrt}(\text{Hz})$





Synchrotron Line

Betatron Lines

Detail of Mod(FT) for H BPMs in A3, Feb 6/05, Coalesced







Detail of Mod(FT) for V BPMs in A3, Feb 6/05, Coalesced







- Synchrotron line present in H but not V.
- 150 GeV expected sync frequency: 80 Hz.

Position for H BPMs in A3, Feb 7/05, Uncoalesced





Position for V BPMs in A3, Feb 7/05, Uncoalesced




- Injection TBT; 150 GeV; 8192 turns.
- Uncoalesced beam. Tuneup shot with large injection mismatches.

Position for HA32 and VA33, Feb 7/05, Uncoalesced



- HV coupling is clear.
- Frequency of envelope is about 260 Hz.

Fourier Transforms of Position Data, Feb 7/05, Uncoalesced





HV Coupling Frequency

Conclusions

- The Tevatron BPM Upgrade has been successfully installed and commissioned.
- Work continues on final calibration, diagnostics, pbar measurements, documentation.
- Thanks to the work of many people in the Computing and Accelerator Divisions at Fermilab.
-

Extra slides

Timing Board



May 16-20, 2005


Production Board

PAC05, Knoxville, TN



Filter Board

- 8 channels
- 53 MHz band-pass filter
- Attenuation Circuit
- Relays/53 MHz diagnostic signal
- Shielding

Production Board



Echotek Board




Production Board

May 16-20, 2005


PAC05, Knoxville, TN

31

Systems are going in!




A3
11/22/04



B3
2/10/05




C3
2/23/05




D3
3/08/05




E3
3/11/05




B0
3/23/05




D0
3/24/05




A2
3/30/05




B2
3/30/05



C2
3/30/05



D2
3/30/05



E2
3/30/05


One Day's Work!




E2
4/8/05



F2
4/8/05



B4
4/8/05



D4
4/8/05



A4
4/8/05



C4
4/8/05

May 16-20, 2005

Stephen Wolbers
PAC05, Knoxville, TN




A1
4/11/05



D1
4/15/05

E4
4/11/05

B1
4/15/05



E1
4/15/05


C1
4/15/05

May 16-20, 2005

Stephen Wolbers
PAC05, Knoxville, TN

Alternative Block Diagram

- BPM signals



Hardware Components


- **Echotek Digital Signal Receiver (150)**
 - Commercial 8 channel 80 MHz 14 bit ADC, DDC, FPGA
 - Exact or similar boards are common to Recycler, Transfer Lines, NUMI, MI BPM projects
- **Front-end Filter Board (150)**
 - 53 MHz band-pass filter, 10 or 20 dB attenuator, relays for diagnostic signal
- **Timing Board (38)**
 - Provides clocks and triggers for Echotek
 - Provides 53 MHz diagnostic signals
- **MVME 2400-0361 Processors, VME subracks, Crate monitoring, cables, test stands, test signals, controls network.**

Software Overview


- **Front-end**
 - Processes Echotek output to provide
 - Closed orbit
 - Turn-by-turn
 - Injection first turn
 - Manages data collection and modes of operation.
- **Online/console applications**
 - Moves data into controls system and applications, libraries and databases.
 - Essentially all applications have been modified to use the new data.
- **Offline/calibration**
 - Provides necessary deconvolution (pbar) and corrections to ensure accuracy and precision of the system.
 - pbar measurements will be available at the front-end.

A3 result - pbar, injection


Reverse Helix Study, VA35 December 8, 2004




Recent Store (Monday 1/17/05) Vertical



Same store - horizontal




p and pbar positions during 1/17/05 store




**Early results-
Still need to
Analyze to see
If it makes
Sense.**

P and pbar resolutions (closed orbit) during 1/17/05 store



Horizontal
~20-25 μm
(thought to
be due to beam
motion)



Vertical
~10-15 μm