MINOS Control Room at Fermilab

MINOS Collaboration Meeting
December 12, 2002
David Boehnlein

The Soudan Control Room

- The Soudan Control Room is multi-purpose
 - Controlling the experiment
 - DAQ, Online Monitoring, DCS, CRL
 - Controlling far detector only at present
 - Constructing the experiment
 - General office space
 - Printers, copier, and administrative amenities
 - Telephone lines
 - Desks, chairs, etc. (never enough)

Outside the Soudan Control Room



Graduate Student in Natural Habitat



Another Model: Mini-BooNE

- Now running in WH10SW
- Computers:
 - One for beam status (4 screens)
 - One for DAQ and CRL
- Television:
 - One for Channel 13
 - One for closed-circuit cameras on critical components (4)

Control Room at Fermilab

- Basic Control Requirements (for both detectors)
 - DAQ
 - Online Monitoring
 - -DCS
 - CRL
 - Other Computers

Control Room Evolution

- Near Term
 - Build and run the far detector with cosmic rays.
- Intermediate Term
 - Run the far detector with cosmic rays.
 - Build and run the near detector with cosmic rays.
- Long Term
 - Run both detectors with the NuMI beam.

DAQ Requirements

The DAQ group will provide computers for run control and monitoring for the near detector.

- DAQ machine runs Linux
- Scheduled to install in 2003.
- Will use VNC to control far detector DAQ.

DCS Computer

- Windows machine running Ifix as at far detector.
 - Separate Ifix windows for each detector (near and far)
 - VNC window allows control of far detector
 DCS machine.
 - MySQL databases are kept on both machines.
 - UMD will provide computer and install Ifix.

Control Room Logbook

- There will be only one logbook for the experiment, maintained on CRL.
 - CRL is running on a "dedicated" computer at Soudan.
 - The WHCR will also have a dedicated CRL machine, but files must be shared, probably via afs.
- Detector construction as well as operation is logged in CRL. A third CRL machine in the Near Detector Hall is highly advisable.

Real Estate in Wilson Hall

- The Beauty Parlor (WH12NW) is to become available after video equipment is moved.
- The north half of this room will provide ample floor space for the WHCR.
 - The room will be divided
 - The other half will be for other use TBD
- Existing phone and ethernet lines may be adequate.

Cost and Schedule

- Estimate \$10k to divide and prepare the room; another \$10k to set up CR.
- Budgetary constraints will probably delay occupancy until late spring 2003.