



# HCAL Constants


Shuichi Kunori  
U of Maryland  
21-July-2003

LHC and CMS  
HCAL plan  
Four Databases

**Caution - All information in these slides are very preliminary and some may be wrong.**



# The LHC




$R = 4.5 \text{ Km}$   
 $E = 7+7 \text{ TeV (pp)}$

crossing rate  
 $= 40 \text{ MHz}$   
(25 nsec)

design luminosity  
 $= 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$


~20 pp interactions  
per crossing  
at design luminosity

$h \rightarrow 4 \mu$  with 20 min. bias evt.





# The CMS detector



Toal weight	12500 t
Overall diameter	15 m
Overall length	21.6 m

**All silicon tracker**  
 micro strips (10M ch)  
 pixel (40M ch)  
 (5.4m long, 2.4m  $\Phi$ :  $|\eta| < 2.4$ )

**Hermetic calorimeter**  
 ECAL: PbWO<sub>4</sub> crystal  
 HCAL: brass+scinti.  
 ( $|\eta| < 3.0$ )

**in 4 Tesla solenoid**  
 (12.5m long, 6m  $\Phi$  in)

**Robust muon system**  
 DT+RPC (barrel)  
 CSC+RPC (endcap)  
 (in iron yoke:  $|\eta| < 2.4$ )

**Fast cerenkov calor.**  
 quartz fiber  
 ( $3 < |\eta| < 5$ )





**Surface buildings and main shaft**



**HCAL barrel**




**Muon barrel yoke**

**Installation of the first muon chamber**



**HCAL/Muon endcap**





**Transfer YB0 (2000t) in 2005**



# HCAL plan

## 2003 June-September

- Calibration runs in the H2 testbeam at CERN
  - All HCAL subdetectors: HB, HE, HF, HO + Crystals

## 2004 Summer-

- Low energy testbeam at H2
  - EC+HC response to low energy beam
  - hadron showers at low energy
- Slice test with EMU, TRIG and DAQ at CMS.
  - Full system test - hardware & software & operation

## 2005

- Transfer HCAL to the under-ground experimental hall.

## 2006

- Test beam (?)
- Integration and commissioning

## 2007

- Data taking



# Conditions Database

All information needed for event reconstruction (HLT/Offline)

HB, HE, HO : scintillator/brass sampling calorimeter

scint. - HPD – QIE (ADC) – HTR (Trig Primitive/pipeline) – L1/DAQ

HF : quartz fiber/iron calorimeter

fibers - PMT – QIE (ADC) – HTR (Trig Primitive/pipeline) – L1/DAQ

Readout channels ~ 10k

Stable detector – no need to update constants frequently, hopefully.

HF gain will decrease due to radiation damage (slow time constant).

## Constants – from ADC counts to GeV

1) Channel response (scint-HPD-QIE)	1	* 10k (ch)
2) QIE calibration (ADC-to-Charge(fC) )	128 (bin)	* 10k (ch)
3) Charge-to-GeV (HB,HE,HO,HF)	1	* 4
4) Pedestal	4 (capid)	* 10k (ch)

+) Channel# – (eta,phi,depth) map



# Configuration DB

All information required to bring the detector in any running mode.

## Run modes:

1) beam, 2) pedestal 3) source calib 4) laser calib 5) LED calib

## Constants (on detector)

HPD/PMT	- HV	1/(HPD or PMT)
CCM	- clock phase	1/(ch)
CalibModule	- mode+	

## Constants (in counting room)

HTR	- pedestal	1/(ch)
	- LUT(ADC-to-GEV)	1LUT/(ch)
	- threshold	1/(ch)
TTC	- timing	





# Integration Database

All information to physically set up the detector and is used for asset tracking

## Detector components: (on detector)

- 1) Absorber
- 2a) Megatile
- 2b) Quartz fiber bundle (HF)
- 3) Optical cable
- 4) RBX(readout box)
  - 4.1) RM{ODU, HPD(PMT), QIE}
  - 4.2) CCM
  - 4.3) Calibration Module
- 5) Cable
- + ) shielding, support (HF)

## Detector components: (in counting room)

- 1) Crate
  - 1.1) HTR
  - 1.2) TTC

**Channel map** (eta,phi,depth)→megatile→optical cable→RM{ODU,HPD,QIE}→HTR(ch)}



# Construction/Hardware DB

**C-DB:** all information about the sub detector construction up to the start of integration.

**H-DB:** all information required for cross checking calibration constants and for detector simulation.

## Detector components: (on detector)

- 1) Absorber - dimension, source tube location (HF)
- 2a) Megatile/fibers - dimension, fiber length, att.length, source scan
- 2b) Quartz fiber bundle (HF) - type
- 3) Optical cable - length
- 4) RBX(readout box) -
- 4.1) RM{ODU, HPD(PMT), QIE} - HPD(PMT) gain, QIE(ADC→fC, timing), map
- 4.2) CCM -
- 4.3) Calibration Module -
- 5) data cable -
- + ) shielding, support (HF)

## Detector components: (in counting room)

- 1) Crate
- 1.1) HTR
- 1.2) TTC

## Calibration Data



**Additional slides**





# Data Flow

>>> front end <<<

## Scint. Lights

->Tile->Fiber1&2->OptCable  
->HPD->Amp->ADC->

## Charge (for 5-10xings)

->(L1Path)  
->(DAQPath)

>>> L1Path <<<

->**HTR** (ch)  
 $E_T(\text{L1Primitive: 8bits:non-linear})$   
->**L1 LUT** (ch)  
 $E_T(4 \times 4 \text{ HcTower: 8bits:linear})$   
->L1Calo  
 $E_T(\text{L1jets}), Et(\text{L1tau}), Et(\text{L1MET})$   
->L1CaloGlobal(**Threshold** (obj))  
->L1Global  
**L1Trigger**

>>> after DAQPath <<<

->**ReadoutAnalyzer** (ch)  
 $E_T(\text{channel})$   
->TowerCreator  
 $E_T(\text{Ec+Hc Tower})$   
->Jet/MET/tauReco  
 $E_T(\text{jetR}), Et(\text{tauR}), Et(\text{METR})$   
->**EtCaloCorrection** (obj)  
(corr. for linearity)  
 $E_T(\text{JetC}), Et(\text{tauC}), Et(\text{METC})$   
->**EtPhysCorrection** (obj)  
(corr. for out-of-cone)  
 $E_T(\text{Parton})$

Calibration/correction  
(ch) - channel by channel  
(obj) - phys. Obj, (jet, tau, MET)



# Tools

## A) Megatile scanner:

- Co<sup>60</sup> gamma source
  - each tile: light yield
  - during construction
- all tiles

## B) Moving radio active source:

- Co<sup>60</sup> gamma source
  - full chain: gain
  - during CMS-open (manual)
- all tiles
- during off beam time (remote)
- tiles in layer 0 & 9

## C) UV Laser:

- full chain: timing, gain-change
  - during off beam time
- tiles in layer 0 & 9
- all RBX

## D) Blue LED:

- timing, gain change
  - during the off beam time
- all RBX

## E) Test beam

- normalization between  
GeV vs. ADC vs. A,B,C,D
  - ratios: elec/pion, muon/pion
  - before assembly
- a few wedges

## F) Physics events

- mip signal, link to HO  
muon
  - calo energy scale (e/pi)  
charged hadron
  - physics energy scale  
Min-bias  
photon+jet balancing  
Z+jet balancing  
jet-jet balancing  
di-jet mass  
W->jj in top decay
- >> non-linear response
- >> pile-up effect



# Scenario (HB/HE)

(same to HF)

## 1) Before megatile insertion

- megatile scanner: **all tiles**
- moving wire source: **all tiles**

## 2.1) After megatile insertion

- moving wire source: **all tiles / 2 layer**
- UV laser: **2 layers/wedge**

## 2.2) After megatile insertion

- test beam: **a few wedges.**

**Absolute calib.  
Accuracy of 2%  
for single particle**

## 3) Before closing the CMS

- moving wire source: **all tiles**
- UV laser & blue LED: **all RBX**  
(do 3, about once/year)

## 4) Beam off times

- moving wire source: **2layer/wedge**
- UV laser: **2 laer/wedge**
- UV laser & blue LED: **all RBX**

**Monitor for change  
with time  
Accuracy < 1%**

## 5) Beam on (in situ)

- jets / tau / MET **ECAL+HCAL**

**once/month**

**a few times/day (?)**