


CMS Virtual Control Room- some thoughts -

Shuichi Kunori U of Maryland 12-Sep-2003

Remote Operation & Monitoring



The LHC




R = 4.5 Km E = 7+7 TeV (pp)

crossing rate =40MHz (25nsec)

design luminosity = 10³⁴cm⁻²s⁻¹


~20 pp interactions per crossing at design luminosity



 $h \rightarrow 4 \mu$ with 20 min. bias evt.



The CMS detector



Toal weight 12500 t Overall diameter 15 m Overall length 21.6 m All silicon tracker micro strips (10M ch) pixel (40M ch)

(5.4m long, 2.4m Φ : $|\eta|$ < 2.4)

Hermetic calorimeter ECAL: PbWO4 crystal HCAL: brass+scinti. (|n| <3.0)

in 4 Tesla solenoid

(12.5m long, $6m \Phi in$)

Robust muon system DT+RPC (barrel) CSC+RPC (endcap)

(in iron yoke: $|\eta| < 2.4$)

Fast cerenkov calor.
quartz fibber
(3<|n|<5)



HCAL barrel

Surface buildings and main shaft




Installation of the first muon chamber









Transfer YB0 (2000t) in 2005





HCAL plan

2003 June-September

- Calibration runs in the H2 testbeam at CERN (TB2003)
 - All HCAL subdetectors: HB, HE, HF, HO + Crystals

2004 Summer-

- Low energy testbeam at H2 (TB2004)
 - EC+HC response to low energy beam
 - · hadron showers at low energy
- Slice test with EMU, TRIG and DAQ at CMS.
 - Full system test hardware & software & operation
- → Remote detector commissioning, debugging & operation
- → "Full" database capability

2005

Transfer HCAL to the under-ground experimental hall.

2006

- Test beam (?)
- Integration and commissioning

2007

Physics data taking



TB2003

TB2003 operation.

- Three months data taking.
- Experts visited CERN for 1~2 weeks (a little longer) to install and commission their detector components, e.g. electronics, DAQ etc.
- People (non-expert) at CERN operated the system.
- Experts debugged and fixed problems, remotely.
- Some people monitored quality of data, remotely.

We used some tools for remote capability.

- web pages. E.g.

http://hpslweb.cern.ch/frame/java/1.1/view110-java.html


- e-logbook (provided by the HEPBook development team at Fermilab).
- 24h/7d VRVS connection.
 - \$100 Logitech camera + Polycom speaker/microphone in an analysis room.
 - a wireless head set and a wireless camera in a control room.
- → daily meeting with experts in Boston, Princeton, Maryland, Texas, Fermilab etc.
- → debug electronics/DAQ in the control room with experts.

Missing:

- remote capability of detector slow control and monitoring.
- → Plan to add these for TB2004 and the slice test.



Operation of CMS





CMS Control Room



Main Control Room (Point 5)

Video Screen









Counting Room





?



FNAL VCR

Video Screen








Console

ACC



Multi-displays/windows

Work/Control Instruction Communication control and status **Video View** Oscilloscope view **DAQ/Trigger status** Alarm (detector monitor/event monitor) **Monitor 1 (detector monitor) Monitor 2 (event monitor 1)** Monitor 3 (event monitor 2) Monitor 4 (event display) Accelerator/beam monitor Accelerator logbook/ATLAS logbook