

Booster Neutrino Beamline Facility Operations Update Present & Future

Thomas R. Kobilarcik

September 23, 2014

Neutrino Beams and Instrumentation, 2014

SEPTEMBER

SUNDAY	MONDAY	TUESDAY	WEDNESDAY	THURSDAY	FRIDAY	SATURDAY
	1	2	3	4	5	6
7	8	9	10	11	12	13
14	15	16	17	18	19	20
21	22	23	24	25	26	27
28	29	30				

PRESENT

Booster Neutrino Beamline and Detectors



MiniBooNE

MicroBooNE


Booster

SciBooNE

Booster Neutrino Beamline




Primary Beamline




Since turning on, BNB has transported 2.1E21 protons.

The horns have pulsed half-a-billion times.


BNB is assessed for 5×10^{12} protons per pulse at 5 Hz average.






Old instrumentation was able to keep beam on target, measure intensity, and measure beam width when needed.


New instrumentation employs low-mass multiwires, allowing continual monitoring of beam shape.



Additionally, we are able to reference multiwires to external coordinate system, allowing us to locate beam position and trajectory in site coordinate system.




Second generation low-mass multiwires. Welded joints, easy access to wire plane, more robust mechanical design. Separation between planes remains at 110 cm and planes retain 0.5 mm pitch. New instrumentation package will be installed when horn is changed.




2 GHz sample rate over entire spill.

Data is recorded every pulse, and is available through the Intensity Frontier Beam Database.



Secondary Beamline and Associated Systems



50 m Absorber

Wells

Berm Cooling System

25 m Absorber


Wells

Service Building
For
Target and Horn

Target and Horn Assembly



Designed by Larry Bartoszek
Built by AD Mechanical Support Target Group
Present engineer is Vladimir Sidorov





Target and horn are built and installed as a single unit, although it is possible to change only the target.

First Horn

- April 28, 2002 to July 28, 2004
- 97 million pulses
- Both horn and target were replaced
- Suspected cause of failure was stagnant water in return line bellows.








- Unstack 6x15 shielding blocks. Blocks needed to be wrapped.
- Remove final focus triplet.
- Lower coffin.
- Remove horn.
- Reverse procedure.


Target and Horn are buried in shielding.
Approximately 12 weeks to change horn, most of which is removing shielding infrastructure.
Target can be changed independently of horn.




Drainage tube removes stagnant water

Second Horn Trivia

- December 2004 to present.
- 1/3 of a billion pulses.
- Two of the six water lines have been valved out due to leakage, but still have adequate cooling.
- Provides new data regarding fatigue of aluminum.
- Water is continually circulated, even during shutdowns and off-target running, to avoid stagnation.




Deployable absorber located 25 m from target.
 Absorber consists of nine one foot thick steel plates, one three foot thick concrete block, and one foot thick instrumented panel.
 Each module is ten feet wide and ten feet tall.
 Originally suspended with high-strength steel chains



AntiNeutrinos/POT unofficial


MiniBooNE Antineutrino Run - Nearline (Unofficial)

Neutrinos/POT (1/1E17)



“problems” is an understatement. A number of chains failed due to hydrogen embrittlement. Several absorber modules fell into decay pipe. All chains were removed and replaced with steel rods.

Absorber **problems**






The 50 m absorber has the same instrumentation as the 25 m absorber

8' 8" of steel "blue blocks", three feet of concrete (10' by 10'), one instrumentation panel, and 26" of steel (more "blue blocks").






The array of loss monitors is read back using the same electronics as we use for the profile monitors.

Over time the signals have degraded. Because the system is buried, there is no access to it.

Profile data is recorded in IF Beams database.




Berm Cooling System



Sept. 23, 2014

NBI2014 -- T. Kobilarcik


24



Closed loop air system. Air is circulated through large HDPE pipes in order to remove heat from berm.

Only able to access cooling pipes through supply and return. Unable to inspect system once buried.

System was first used in 2013 for off-target running. Temperature probes were inserted through LMC pipe near absorber.



Decay pipe buried in 12 to 15 feet of aggregate.

Aggregate is surrounded by two impermeable liners.

Three drainage systems.

Each drain connects to two monitoring wells, one upstream and one downstream.

Expect water in exterior drain tile, but inner and interstitial drains should remain dry. Early on we found they did not, implying there is a leak in the liner




service building

liner


upstream wells

downstream wells


Replacing the pump requires pulling the pump and pipe with a crane or lift bucket.



May				June				July				August				September				October				November			
4/28	5/5	5/12	5/19	5/26	6/2	6/9	6/16	6/23	6/30	7/7	7/14	7/21	7/28	8/4	8/11	8/18	8/25	9/1	9/8	9/15	9/22	9/29	10/6	10/13	10/20	10/27	11/3




Planned Facility Modifications



Run beam off target.
 Hang two SWICs (Segmented Wire Ionization Chamber) upstream and downstream of 25 m absorber.
 This will allow one to tie the primary beam trajectory to the site coordinate system.
 This is a one-time measurement.

Planned for this year, after the shutdown.





Install impermeable barrier to keep water away from liner.

Over the past year a temporary tarp was placed over the berm and adjoining area. This worked well in keeping water out of the tear.

New barrier is permanent. About one foot of dirt will be remove, the barrier will be installed, and the dirt will be replaced. Drain tile will be installed around the toe of the berm.

Work starts this week

Possibilities ...

Room for More Detectors

New Far Detector ?

MiniBooNE


MicroBooNE

New Near Detector ?

SciBooNE

Booster Neutrino Beamline





Modify first and last modules to contain retractable wire chambers.

Due to how the absorber system is build, one would need to lower all the absorbers, pull out the first and last modules, replace them with modified modules, then lift all back in place.


Alignment would be challenging.

drive mechanism

notched and slotted steel absorber

drive rods

wire chamber






Dig up and rebuild the 50 m absorber.

Replace blue blocks with steel plates in order to eliminate cracks.

Install a hadron monitor, similar to that in the NuMI beamline.

Build a structure to allow access.

This would be challenging. The liner would have to be opened and then resealed. The aggregate surrounding the absorber is radioactive. The blue blocks are radioactive. However, this option would allow one to know accurately the direction of the primary beam.





Re-optimize horn.

Change target material.

Change shape of inner conductor.


The present target and horn system is optimized for MiniBooNE. The target size and material can be changed to suit the need of future experiment. The shape of the inner conductor can also be changed.



Add a second horn. But...

Where do you put it?


Most of this area is filled support infrastructure




Sump pit (blue circle)

Final focusing triplet (light blue)

Concrete shielding blocks, which form part of the floor of the enclosure (green hatch)



Steel shielding (red hatch)



Use smaller magnets for triplet, which allows one to push beamline upstream?


Fill free space in target hall with steel shielding?

Move infrastructure into tunnel?

How does one route the striplines for the second horn?

Does one need to re-route striplines for the first horn?

Where does one put the power supply for the second horn?





Build a new beamline.

Ending Comments



- The Booster Neutrino Beamline has run successfully for the past 12 years.
- BNB will run to support MicroBooNE.
- Thought should be given as to what upgrades are desirable for an expanded short baseline neutrino program.

Backup Slides


Location

50 m absorber

MI12 (target location)



Beamline – Block Diagram



The Booster Neutrino Beamline was designed by Al Russel

Beamline -- Schematic





Figure 2.1: Beamline schematic and function. Elements are listed in Table 2.1.

Optics




8 GeV.

Designed to deliver $5E12$ protons per pulse at 5 Hz average.


~40 degree phase advance per cell.

Optics




Up to 12 m horizontal and 5 m vertical dispersion.
Use large aperture (6-3-120) dipoles.
Zero dispersion at target.

Optics




- Beam was bumped upstream, both vertically and horizontally.
- Quadrupole transfer functions were adjusted to match data.

Optics



- Known lattice functions at 851 are propagated down beamline.
- Good match between prediction and measurement.



Changed momentum by inserting a piece of copper. Able to accurately predict perturbed trajectory.

Keeping Beam on Target -- AutoTune

- Change the current on a trim magnet and measure the movement on downstream BPMs:

$$\begin{aligned}\Delta i_1 &\rightarrow \Delta x_1, \Delta x_2, \Delta x_3 \\ \Delta i_2 &\rightarrow \Delta x_2, \Delta x_3\end{aligned}$$

- Leads to a linear equation:

$$\Delta \vec{x} = \begin{pmatrix} \frac{\Delta x_1}{\Delta i_1} & \dots & \frac{\Delta x_1}{\Delta i_n} \\ \vdots & \ddots & \vdots \\ 0 & \dots & \Delta x_n / \Delta i_n \end{pmatrix} \Delta \vec{i}$$

or


$$\Delta \vec{x} = \mathbf{M} \Delta \vec{i}$$

- Choose correctors and BPMs so that “M” is invertible.
- Can now solve for change in current given needed correction to positions:

$$\Delta \vec{i} = \mathbf{M}^{-1} \Delta \vec{x}$$


- To insure convergence:
 - Add tolerance to ideal position.
 - Make a fraction of the full correction.


Modification




- Added drainage tube to return lines at five o'clock and seven o'clock position.
- Minimizes stagnant water.

Modification







The target and horn are located in MI12B, accessed through the MI12 service building.



Target/Horn in Target Pile



Target Pile




Well Pump

Transducer



Three upstream wells



Three downstream wells